

1 DISPOSAL OF WASTES

- 1.1 Do not dispose of waste or volatile materials, such as mineral spirits, oil or paint thinner into waterways, storm or sanitary sewers.
- 1.2 Remove, legally dispose of off site all surplus materials, debris, waste, existing materials, items not required by Engineer, not required for Work, resulting from excavations, demolition, removals. Do not bury rubbish and waste materials on site. Fires and burning of rubbish on site is not permitted.

2 DRAINAGE

- 2.1 Provide temporary drainage and pumping as necessary to keep excavations and site free from water. Do not pump water containing suspended materials into waterways, sewer or drainage systems.
- 2.2 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authority requirements.

3 SITE CLEARING AND PLANT PROTECTION

- 3.1 Protect trees and plants on site and adjacent properties. Restrict tree removal to those designated. Wrap in burlap, trees and shrubs adjacent to construction work, storage areas and trucking lanes. Encase with protective wood framework from grade level to height of 2000 mm.
- 3.2 Protect roots of designated trees to dripline during excavation and site grading to prevent disturbance or damage. Avoid unnecessary traffic, dumping and storage of materials over root zones.
- 3.3 Minimize stripping of topsoil and vegetation.

4 POLLUTION CONTROL

- 4.1 Maintain temporary erosion and pollution control features installed under this contract.
- 4.2 Control emissions from equipment and plant to local authorities emission requirements.
- 4.3 Provide temporary enclosures to prevent sandblasting and other extraneous materials from contaminating air beyond application area.
- 4.4 Cover or wet down dry materials and rubbish to prevent blowing dust and debris. Provide dust control for temporary roads.