

**1. GENERAL**

1.1. The work of this section includes the provision of all design, labour, materials, equipment and services required to fabricate and install natural gas supply as required for a complete project. The work includes, but is not necessarily limited to, the items referenced herein:

1.1.1. Natural gas supply.

**2. DESIGN**

2.1. Fuel source, natural gas:

2.1.1. Provide required service connections and piping at gas main, meters and regulators at buildings to ensure adequate gas supply to the building.

2.1.2. Gas shut-off valve shall be located at or near exterior ground level entrance to building. Shut-off valve to be protected against damage.

2.1.3. Install in accordance with [CAN/CGA-B149.1-M95] and in accordance with local utility requirements.

**3. MATERIALS**

3.1. All materials must meet the latest codes and standards based on the type of application.

**4. INSTALLATION**

4.1. Installation shall be done to the latest codes and standards and must be acceptable to the authorities having jurisdiction.

***End of Section***